

Scandia Valley TWP | Scandia Valley, MN

38'x63" Outside Dia. Snap Tite

Owner

Scandia Valley Township

Contractor

Marvin Tretter Inc.

Consulting Engineer

Morrison County Public Works

Application

Existing 72" CMP exceeded the life expectancy and a 63" outside diameter was used to slip line, bulk head, and grout annular space.

Why corrugated steel pipe from TrueNorth Steel?

Durability and ease of installation within the current conditions.

Project Challenges

Installed in current water depth of estimated 3'. Road needed to remain open during construction. Only one access in and out.

Other TrueNorth Steel products used

Two 60" T2 Aluminized End Sections

BEFORE



AFTER

